this account this contract has to be cancelled and other arrangements made for the excution or completion of the work. He will also be held liable for any loss or extra amount of expenditure that may have to be incurred or paid and such amount would be recovered from him either as arrears of land revenue or in any manner considered suitable.

8. No interest will be allowed on the security amount deposited with the Chief Auditor, Mysore State Railway, nor on any money retained by the Administration.

9. The accepted rate will hold vaild till the entire work is completed and claims for enhanced rates will not be entertained under any circumstances for tendered items of work.

Schedule.

Approximate quantities of works to be done for improvements to Labourers' Quarters near Railway Central Workshops and drainage arrangements at Mysore South.

Sl. No.	Items of work	Unit	Quantity	Rate in figures	Rate in words
	IMPROVEMENTS TO QUARTERS.				
1	Excavation in all soils including excavated earth and tamping	1000 C.ft.	2,587	...	...
2	Filling in excavated earth including tamping	,,	888	...	...
3	Concrete of broken granite jelly in railway cement 1 : 3 : 6	100 C.ft.	216	...	...
4	Masonry contractor's burnt brick in lime founds and plinth	,,	2,317	...	...
5	Do in prepared mud	,,	3,566	...	...
6	Dressed stone lintels 4" to 6" thick including fixing	C.ft.	172	...	...
7	T. W. doors with battened shutters including all fittings complete as per marryat's specifications	S.ft.	954	...	...
8	T. W. windows with battened shutters ⅜" dia. M. S. bars and all fittings complete as per marryat's specifications	,,	544½	...	...
9	Fixing doors including frames	Each	54	...	...
10	Fixing windows do	,,	66	...	...
11	Lifting and fixing rails in buildings	Ton	14·59	...	...
12	Fixing deptl. asbestos sheets on roofing with depth bolts. and nuts	100 S.ft.	5,184	...	...
13	T. W. wrought and put up including wood oiling two coats	C.ft.	268·16	...	...
14	Roofing with contractor's first class Mangalore tiles on teak reepers 2"×1" including chunam borders 9" wide ×4½" thick teakwood wind tiles 2"×2" etc., complete.	100 S.ft.	7,708	...	...
15	Setting contractor's ridge tiles in lime mortar	100 R.ft.	800	...	...
16	Supplying and fixing ventilating tiles	Each	24	...	...
17	Do glass tiles Mangalore pattern	,,	24	...	...
18	Fixing gutters with Deptl. G. I. sheets	S.ft.	2,486	...	...
19	Plastering in lime brick masonry	100 S.ft.	13,958	...	...
20	White washing two coats	,,	13,958	...	...
21	Flooring with 1½" thick cement concrete on 3" lime concrete including plastering ½" thick (cement supplied departmentally).	,,	7,987	...	...
22	Painting two coats with contractor's chocolate paint	,,	4,810	...	...
23	Providing sinks 2'×2'	Each	66	...	...
24	Providing ovens	,,	66	...	...
25	Supplying and fixing G. I. down water pipes 4" dia. with contractor's materials	R.ft.	742	...	...
26	Providing masonry drain 6" with brick in lime at sides, lime concrete 4" thick at bottom including plastering in depti cement and covering with 4" thick one line dressed granite slabs complete.	,,	1,150	...	...
27	Plastering in Railway cement	100 S.ft.	504	...	...
28	Providing washing place, one line dressed slabs 4" thick fixed on the top of burnt brick in lime masonry 2½' high by 1½' wide including plastering in Railway cement with necessary slope.	Each	66	...	...
29	Lime mortar bunds 9"×4½" on roofs including plastering	100 R.ft.	909	..	
30	Dismantling masonry (brick in mud)	100 C.ft.	1,450	...	...
31	Do do (in lime)	,,	192	...	...
32	Removing and refixing windows including frames	Each	18	...	...
33	Do do doors do		51	...	...
34	Shifting existing mortar and pestle in building to the new places including fixing	,,	12	...	...
	II. PROVIDING DRAINAGE ARRANGEMENTS AND CISTERNS.				
1	Excavation in all soils and spreading the excavated earth including levelling	1000 C.ft.	3,226	...	...
2	Concrete of granite broken jelly in railway cement 1 : 3 : 6	100 ,,	1,372	...	...
3	Dressed stone lintels 4" to 6" thick including fixing...	,,	4	...	...
4	Masonry contractor's burnt brick in railway cement	100 ,,	2,890	...	...
5	Do do in lime founds and plinth	,,	225	...	...
6	Plastering in railway cement	100 S.ft.	17,655	...	...
7	Supplying and fixing stoneware pipes 4" dia. in railway cement	R.ft.	360	...	...
8	Supplying and fixing C. I. frame with lid at top 2 ft. dia. on manhole	Set	7	...	...
9	Supplying and fixing gully traps	Each	7	...	...
10	Pipe trenching including filling in	100 C.ft.	2,880	...	...
11	Flooring with 1½" cement concrete on 3" thick lime concrete including plastering in railway cement ½" thick.	100 S.ft.	3,400	...	...

N.B.—Contractor should make his own arrangements for water. All debris after completion of work should be removed at contractor's cost. Cement G. I. sheets, plain for gutters, asbestos sheets will be supplied departmentally free of cost to the contractors. Payment for doors and windows will be made on the clear dimensions between frames.

1025 S. RAJAGOPAL, Ag. *Dist. Engr.*

OFFICE OF THE ASSISTANT DIRECTOR OF AGRICULTURE, KOLAR.

Auction Notification dated 3rd February 1949.

It is hereby notified for the information of the public that about 500 unserviceable gunny bags will be auctioned on 1st March 1949 between 11 A.M. and 2 P.M. at the premises of the Office of the Assistant Director of Agriculture, Kolar Circle, Kolar. Intending bidders have to deposit Rs. 25 in advance and be present there at the time The deposit excepting in the case of the successful bidder will be returned. The highest bidder will have to immediately deposit the amount and take the gunnies after approval is communicated.

8756 C. M. REVANNA, *Asst. Director.*

TUMKUR DISTRICT.

(CIVIL SUPPLIES BRANCH).

Notification dated 1st—3rd February 1949.

No. A. Y. 7—48-49. Sealed tenders are invited from the intending contractors for the following items of work in Tumkur Town relating to the District Reserve godowns.

I. Loading, Un-loading and Conveyance.

(a) Un-loading the bags from the wagons and (i) conveyance to the Depot located in the Railway Station yard and stacking (ii) conveyance to Nissen Shed godown just outside the Station Yard and stacking (iii) conveyance to any othe depot within Municipal limits and stacking (rate per bag to be mentioned).

(b) Un-loading of bags from Wagon, weighment at the platform scale and conveyance and stacking at (i) Railway Station Depot (ii) Nissen Shed go-downs (iii) any other go downs within Municipal limits (rate per bag to be mentioned)

(c) Loading and un-loading charges for grains conveyed by Government lorries including stacking (rate per bag).

II. Weighing, bagging and stacking at the Depot.

(a) Weighment of grains at the Depots in the scale provided per bag and stacking.

(b) Measuring, rebagging stitching and stacking in rows—per bag (i) including materials for stitching (ii) excluding materials for stitching.

III. Empty gunnies.

(a) Un-loading of empty gunnies from wagons and conveyance to (i) Railway Station Depot, (ii) Nissen Shed godown (iii) any other godown within Municipal Limits and stacking (per 100 bags).

(b) Loading of empty gunnies into wagons after conveying the same from (i) Railway Station Depot, (ii) Nissen Shed godown, (iii) Any other godown within Municipal Limit (per 100 bags).